

**Dr. Y. S. Parmar University of Horticulture and Forestry,  
Regional Horticultural Research and Training Station,  
Bajaura, Kullu (HP) 175 125**

No.UHF/RHRS/BJR/-MIDH-755-53/- **800-805**

Dated: **22-01-2026**

From:

Associate Director (R&E)

To

-----As per Overleaf-----  
-----

**Subject: Quotation for the Construction of Polyhouse (17m x 16m) .**

Sir,

Sealed quotations addressed to the undersigned are invited for the construction of polyhouse with following specifications. The quotations must reach this office on or before 16-02-2026.

Sr. No.	Name of Items/Articles	Remarks
1.	<p><b>Polyhouses (17m x 16 m)</b></p> <p><input type="checkbox"/> <b>Structure / Framework:</b> Made of GI (Galvanized Iron) pipes (63 mm dia 2 mm thick, 48 mm dia 2mm thick) 42 mm dia 2mm thick, 32 mm dia 2mm thick, 25 mm dia 2mm thick) providing strength, durability, and corrosion resistance.</p> <p><input type="checkbox"/> <b>Covering Material:</b> UV-stabilized polyethylene sheet (200 micron), anti duct, suitable for long-term protected cultivation and optimized light transmission.</p> <p><input type="checkbox"/> <b>Shape &amp; Design:</b> Semi-circular arched (D-type) design, ensuring good air circulation, rainwater drainage, and wind resistance.</p> <p><input type="checkbox"/> <b>Span Configuration:</b> Two-span (2-span) structure, allowing larger cultivation area with fewer internal supports.</p> <p><input type="checkbox"/> <b>Ventilation System:</b> Naturally ventilated, Side and top vents Open windows of 1.2 × 1.2 m<sup>2</sup> provided on both sides on top of the structure</p> <p><input type="checkbox"/> <b>Side Covering:</b> Both side walls covered with insect-proof net, preventing pest entry while allowing airflow.</p> <p><input type="checkbox"/> <b>Irrigation &amp; Climate Support:</b> Drip irrigation system, Foggers / misting system for humidity and temperature management</p> <p><input type="checkbox"/> Side wall (gutter) height: 4.0 m Central ridge height: 5.5 m</p>	<p>➤ Rate should be coated including GST and labour/ installation charges etc..</p>

**Terms and Conditions**

1. Rates should be quoted for Regional Horticultural Research Station, Bajaura, District Kullu Himachal Pradesh.
2. Rates should be quoted separately for each item.
3. Rates should be inclusive of packing and forwarding charges.
4. Supply/ construction shall have to be made immediately after the receipt of supply/ construction order.
5. The quotations received after due date are likely to be rejected and the university will not be responsible for postal delays and wrong deliveries.
6. If the material is not supplied within the stipulated period, The Associate Director(R&E) reserves the right to impose any penalty.
7. The envelope containing the quotation must be super-scribed as quotation for the supply/ construction of Polyhouse (17m x 16m) due on 16-02-2026.
8. The rates shall be valid for a period of 6 months from the date of opening of quotations.

  
Associate Director(R&E) **22-01-26**